LICENSE PLATE READER CAMERA INSTALLATION

CASE NUMBER: 00259323

PERMITTING JURISDICTION:

VILLAGE OF LONG GROVE

CONTACT LIST

PERMITTING

ERIC KRAVITZ ERIC.KRAVITZ@FLOCKSAFETY.COM

PROJECT MANAGER


CHELSEA DAY CHELSEA.DAY@FLOCKSAFETY.COM

SEE APPROVED PERMIT FOR LISTED INSPECTOR

DRAWING INDEX			
T.01	COVER SHEET & LOCATION MAPS		
T.02	SYMBOLOGY & ABBREVIATIONS		
GN.01 - GN.03	GENERAL NOTES		
A.01 - A.2	PLAN DRAWINGS		
SPEC.01 - SPEC .02	EQUIPMENT & FOUNDATION DETAILS		




STATE OF ILLINOIS



THIS DOCUMENT HAS BEEN DRAWN BASED OFF THE MOST RECENT AVAILABLE DATA & AERIAL IMAGERY. THIS INCLUDES RIGHT OF WAY, EXISTING UTILITIES, & PRIVATE PROPERTY LINES. IT REMAINS THE RESPONSIBILITY OF OTHERS TO VERIFY & CONFLICTS ABOVE & BELOW GRADE. ALL CONSTRUCTION TO FOLLOW VILLAGE OF LONG GRAVE GENERAL GUIDELINES. DO NOT SCALE DRAWINGS. CALL 811 PRIOR TO DIGGING

LINE TYPES



RIGHT OF WAY
EDGE OF PAVEMENT
SIDEWALK
CENTER LINE
GAS
WATER
TELEPHONE
ELECTRIC
SANITARY SEWER (SEW)
STORM DRAIN
FENCE
UNKNOWN UTILITY
RAILROAD

SYMBOLOGY

	FLOCK CAMERA - EXISTIN
	FLOCK CAMERA - PROPC
\otimes	POLE - PROPOSED
\otimes	POLE - EXISTING
(НН)	HANDHOLE - EXISTING
НН	HANDHOLE - PROPOSED
PED	PEDESTAL - EXISTING
MH	MANHOLE - EXISTING
-EH-	FIRE HYDRANT - EXISTIN
-∰-	WATER VALVE - EXISTING
ŀĠŀ	GAS VALVE - EXISTING

THIS DOCUMENT HAS BEEN DRAWN BASED OFF THE MOST RECENT AVAILABLE DATA & AERIAL IMAGERY. THIS INCLUDES RIGHT OF WAY, EXISTING UTILITIES, & PRIVATE PROPERTY LINES. IT REMAINS THE RESPONSIBILITY OF OTHERS TO VERIFY & CONFLICTS ABOVE & BELOW GRADE. ALL CONSTRUCTION TO FOLLOW VILLAGE OF LONG GROVE GENERAL GUIDELINES. DO NOT SCALE DRAWINGS. CALL 811 PRIOR TO DIGGING.

	\bigcap			
		[THIS SPACE LEFT IN	ITENTIONALL	Y BLANK FOR STAMP]
				MEADOWS
		1237 ANTI GRO	IETAM VE, IL 6	DR, LONG 60047
	\geq			
)	_	la =		c .
	†	TOCK	(S	afety
	11			OAD SUITE 210
		ATLAN	ITA, GA	30318
	REV	DATE	BY	DESCRIPTION
	-	-	-	-
	-	-	-	-
	-	-	-	-
	0	- 12/15/2022	- DAW	PRELIM
	\geq			
	I HEARE MY I	DIRECT SUPERVISION TH	HAT I AM A DU	EPARED BY MYSELF OR UNDER JLY REGISTERED ENGINEER ATE OF ILLINOIS.
	\geq			
	\leq	[THIS SPACE LEFT IN	ITENTIONALL'	Y BLANK FOR STAMP]
	LI		TE REA TALLA1	DER CAMERA TION
		PERMITTIN	IG JUR	00259323 ISDICTION:
	\subseteq	VILLAGE		IG GROVE
			_	
		OVER SHEE	T & LO	
	C C	OVER SHEE SHEET: T.02	<u>T & LO</u>	REV:

GENERAL & CONSTRUCTION NOTES

1. FLOCK SAFETY SHALL BE RESPONSIBLE FOR LOCATING ALL UNDERGROUND UTILITIES 48 PRIOR TO CONSTRUCTION.

2. CONTRACTOR SHALL BE RESPONSIBLE TO APPLY AND OBTAIN AN APPROVED TRAFFIC CONTROL PLAN IN ACCORDANCE WITH MUTCD AND LOCAL STANDARDS AS REQUIRED.

3. CONTRACTOR SHALL BE RESPONSIBLE TO RESTORE ALL DISTURBED AREAS TO ORIGINAL CONDITION TO STATE DEPARTMENT OF TRANSPORTATION AND LOCAL AGENCY SATISFACTION AT NO ADDITIONAL COMPENSATION.

4. ALL WORK SHALL CONFORM TO ALL APPLICABLE ELECTRICAL CODES EXCEPT WHEN SATE DEPARTMENT OF TRANSPORTATION AND LOCAL AGENCY STANDARDS SUPERSEDE.

5. ALL CONSTRUCTION SHALL BE IN ACCORDANCE WITH STATE AND LOCAL AGENCY SPECIFICATIONS UNLESS SPECIFICALLY STATED OR SHOWN OTHERWISE HEREIN.

6. THE WORK INVOLVING INSTALLATION OF FLOCK SAFETY ALPR CAMERAS INVOLVING TEMPORARY LANE CLOSURES ARE TO BE DONE BETWEEN THE HOURS OF 8:00AM AND 5:00PM, MONDAY THROUGH FRIDAY UNLESS OTHERWISE STATED BY THE DEPARTMENT.

7. WHEN INSTALLING FLOCK SAFETY PROVIDED POLES, A MINIMUM OF 2' SEPARATION SHALL BE MAINTAINED FROM ALL EXISTING UTILITIES AND STORM DRAIN STRUCTURES.

8. IF THE PROPOSED UTILITY CANNOT BE INSTALLED PER THE APPROVED PERMITTED PLAN AND BY GENERAL SPECIFICATIONS, A REVISED PLAN MUST BE PROVIDED TO THE DEPARTMENT FOR REVIEW AND APPROVAL PRIOR TO THE INSTALLATION OF PRODUCTS OR MATERIALS AT THE GIVEN LOCATIONS WHERE CONFLICTS OCCUR.

9. NO PEDESTRIAN PATHWAY IS TO BE REMOVED, BLOCKED, OR DISTURBED WITHOUT HAVING A SUFFICIENT DESIGNATED TEMPORARY PEDESTRIAN PATHWAY WITH ALL APPROPRIATE PEDESTRIAN MAINTENANCE OF TRAFFIC SIGNS IN PLACE PRIOR TO PATHWAY BEING AFFECTED.

10. ALL TEMPORARY PEDESTRIAN PATHWAYS MUST BE FIRM AND UNVIELDING.

11. ANY SIDEWALK DISTURBED WILL BE REPLACED BY SECTION WITHIN 72 HOURS TO GENERAL SPECIFICATIONS.

12. THE GENERAL RETAINS THE RIGHT TO MAKE ALTERATIONS TO THE PERMIT. ATTACHED SKETCH OR CHARACTER OF WORK AS MAY BE CONSIDERED NECESSARY OR DESIRABLE DURING THE PROGRESS OF THE WORK FOR SATISFACTORY COMPLETION OF THE PROPOSED CONSTRUCTION.

13. THE PERMITTEE SHALL NOTIFY THE GENERAL OF DATE OF COMPLETION, REQUEST A FINAL INSPECTION AND A NOTICE OF FINAL ACCEPTANCE.

14. ALL CONSTRUCTION AND/OR MAINTENANCE ON THE GENERAL RIGHT OF WAY SHALL CONFORM TO THE FEDERAL MANUAL ON UNIFORM TRAFFIC DEVICES, THE GENERAL ROADWAY AND TRAFFIC DESIGN STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION, PLANS PREPARATION MANUAL AND DRAINAGE MANUAL.

15. ANY SIDEWALK DAMAGED AS A RESULT OF WORK BEING PERFORMED IN ASSOCIATION WITH THE PERMITTEE AND CONTRACTOR SHALL BE REMOVED AND REPLACED.

16. THE CONTRACTOR SHALL HAVE AN AUTHORIZED PERSON AVAILABLE AT/OR NEAR THE WORK SITE ON A 24 HOUR BASIS, 7 DAYS A WEEK IN ORDER TO ADDRESS EMERGENCY ISSUES ASSOCIATED WITH THE PROJECT.

17. NO STOCKPILING, STORING OR SEMI PERMANENT USE OF THE RIGHT OF WAY IS AUTHORIZED UNLESS SPECIFICALLY IDENTIFIED WITHIN THE PERMIT.

18. NO WORK SHALL BE PERFORMED DURING ANY STATE OR FEDERAL HOLIDAYS UNLESS OTHERWISE APPROVED BY THE GENERAL.

19. THE PERMITTED WORK SCHEDULE IS DEFINED AS MONDAY THROUGH FRIDAY 8:00AM TO 5:00PM UNLESS OTHERWISE NOTED WITHIN THE PERMIT. ANY WORK DESIRED OUTSIDE OF THIS PERIOD MUST BE REQUESTED IN ADVANCE AND APPROVED BEFORE WORKING THE ALTERNATE SCHEDULE.

20. THE DEPARTMENT RESERVES THE RIGHT TO MAKE ADJUSTMENTS TO ANY PERMITTED METHODS OF INSTALLATION, SCOPE OF WORK AND RESTORATION THAT MAY BE REQUIRED TO POSITIVELY SUPPORT LIFE, SAFETY AND ENVIRONMENTAL WELL BEING OF ALL USERS OF THE TRANSPORTATION SYSTEM

GENERAL & CONSTRUCTION NOTES CONTINUED:

21. PERMITTEE SHALL NOT BEGIN ANY WORK ALONG GENERAL RIGHT-OF-WAY UNTIL THE INPECTION OF THE PERMIT ARE MET.

22. PRIOR TO CLOSING A LANE, THE PERMITTEE SHALL PROVIDE A SUTIABLE TRAFFIC CONTROL PLAN AS PER FEDERAL MANUAL TRAFFIC CONTROL STANDARDS DEPICTING ALL WORK BEING DONE. THE UTILITY OWNER IS NOT REQUIRED TO REPORT LANE CLOSURES FOR EMERGENCIES.

23. IT WILL BE THE RESPONSIBILITY OF THE PERMITTEE TO REPAIR ANY DAMAGE TO GENERAL FACILITIES AND/OR PRIVATE PROPERTY CAUSED BY CONSTRUCTION OF THE PRO1FCT

DESIGN NOTES:

POLE AND FOUNDATION DESIGNED PER CURRENT STANDARD SPECIFICATIONS FOR STRUCTURAL SUPPORT FOR HIGHWAY SIGNS, LUMINAIRES AND TRAFFIC SIGNALS.

POLE DESIGN WIND SPEED IS 85 MPH, 110 MPH, 130 MPH, AND 150 MPH 2 BASED ON A 300-YEAR MRI

3 CONCRETE SHALL HAVE A MINIMUM 28-DAY DESIGN STRENGTH OF 3000 PSI, AND HAVE AT LEAST 505 POUNDS OF CEMENTITIOUS MATERIAL PER CUBIC YARD.

PROVIDE A FLAT BEARING SURFACE ON TOP SURFACE ON TOP SHAFT BELOW THE POLE BASE. SLOPE TOP SURFACE OF CONCRETE SHAFT OUTSIDE OF POLE BASE TO DRAIN AWAY FROM POLE.

5. DO NOT USE THIS DETAIL FOR SITES WHERE SOIL CONSISTS OF SOFT CLAY. PEAT OR ANY OTHER SOIL WHERE A SMALL DIAMETER REBAR (#5 OR SMALLER) OR METAL PROBE PENETRATES EASILY TO 6" OR MORE OF DEPTH WHEN THE FULL WEIGHT OF A PERSON IS APPLIED.

ADA COMPLIANCE NOTES:

ALL SIDEWALK CONSTRUCTION SHALL BE IN ACCORDANCE WITH ADA TITLE II AND ALL FEDERAL, STATE, AND LOCAL STANDARDS.

USE STANDARD WATCH MANUAL PLANS FOR PEDESTRIAN CONTROL PLANS FOR CLOSURE OF SIDEWALK.

3. MINIMUM SIDEWALK CLEAR PEDESTRIAN ACCESS ROUTE (PAR) IS 48" WIDE.

NO OBSTRUCTION IS PERMITTED ALONG THE WIDTH OF THE SIDEWALK UP TO 7'-0" IN HEIGHT.

COUNTY NOTES:

CURRENT A.D.A. STANDARDS SHALL BE UPHELD AT ALL TIMES.

CONTRACTOR SHALL MAINTAIN ACCESS TO ALL ADJACENT PROPERTY IN THE VICINITY OF THE CONSTRUCTION

CONTRACTOR SHALL PROVIDE SAFE ACCESS PER CURRENT GENERAL STANDARDS FOR ALL PEDESTRIAN TRAFFIC REGULATIONS ON ALL EXCAVATIONS OPENED IN THE TRAFFIC ZONE CONTROL AREA.

CONTRACTOR SHALL RESTORE RIGHT-OF-WAY TO EQUAL OR BETTER CONDITION UPON COMPLETION OF WORK.

1						
		[THIS SPACE LEFT IN	TENTIONALLY	BLANK FOR STAMP]		
		COUNTRY				
		1237 ANTI GRO	ETAM I VE, IL 6			
	11	70 HOWELL I ATLAN	VILL RO			
	REV	DATE -	BY -	DESCRIPTION -		
	-	-	-	-		
	-	-	-	-		
	-	-	-	-		
	0	12/15/2022	DAW	PRELIM		
	I HEARE MY	BY CERTIFY THIS DOCUM DIRECT SUPERVISION TH UNDER THE LAW	HAT I AM A DU	EPARED BY MYSELF OR UNDER LY REGISTERED ENGINEER TTE OF ILLINOIS.		
	[THIS SPACE LEFT INTENTIONALLY BLANK FOR STAMP]					
		INST CASE NUI PERMITTIN	TALLAT MBER: IG JURI	00259323 SDICTION:		
	\subseteq	VILLAGE (JF LON	G GROVE		
	С		T & LOO	CATION MAPS		
		SHEET: GN.01		REV:		

GENERAL NOTES:

1. ALL WORK PERFORMED WITHIN THE GENERAL RIGHT-OF-WAY SHALL BE IN ACCORDANCE WITH THE CURRENT GENERAL STANDARDS.

2.SHOULD A CONFLICT ARISE BETWEEN THE DETAILS SHOWN IN THE PLANS AND THE DEPARTMENT OF TRANSPORTATION STANDARDS, THE ENGINEER/PERMITTEE SHALL IMMEDIATELY CONFER WITH THE TRANSPORTATION STANDARDS, THE ENGINEER/PERMITTEE SHALL IMMEDIATELY CONFER WITH THE DEPARTMENT'S ENGINEER IN ORDER TO RESOLVE THE DISCREPANCY. IN NO CASE WILL ANYTHING LESS THAN THE DEPARTMENTS MINIMUM STANDARDS BE ALLOWED.

3. ALL TRAFFIC STRIPING AND MARKINGS ARE TO BE LEAD-FREE, NON-SOLVENT BASED THERMOPLASTIC.

4. ALL DISTURBED AREA WITHIN THE RIGHT-OF-WAY WILL BE RESTORED TO ORIGINAL OR BETTER CONDITION BY GRADING AND SODDING IN AREA DISTURBED.

5. BURNING OF ANY MATERIAL OR DEBRIS IS PROHIBITED IN GENERAL RIGHT-OF-WAY.

6. ALL LANES MUST BE OPENED FOR TRAFFIC DURING AN EVACUATION NOTICE OF A CATASTROPHIC EVENT AND SHALL REMAIN OPEN FOR THE DURATION OF THE EVACUATION OR EVENT.

7. THE CONTRACTOR SHALL NOTIFY JURISDICTION PRIOR TO BEGINNING ANY CONSTRUCTION WITHIN GENERAL RIGHT-OF-WAY AS PER ISSUED PERMIT.

8. ALL AREAS WITHIN GENERAL R/W DISTURBED BY CONSTRUCTION SHALL BE RE-GRADED AND SODDED WITH LIKE-KIND SOD WITHIN (7) DAYS.

1.0 SCOPE OF WORK

1.1 THIS PROJECT SHALL CONSIST OF THE FOLLOWING OPERATIONS:

THE WORK PACKAGE IS FOR THE INSTALLATION OF FLOCK SAFETY ALPR CAMERAS WHICH INCLUDES BUT IS NOT LIMITED TO: FLOCK SAFETY PROVIDED POLES, POLE MOUNTED SOLAR PANELS, AND EXTERNAL BATTERY PACKAGES.

2.0 DRAWINGS

2.1 THE WORK SHALL BE PERFORMED IN STRICT ACCORDANCE WITH THE FOLLOWING ATTACHED DRAWINGS THAT ARE HEREBY MADE A PART OF THE STATEMENT OF WORK, BY THIS REFERENCE.

2.2 INSTALLER SHALL RECEIVE FLOCK SAFETY MATERIALS AT A FLOCK SAFETY LEASED WAREHOUSE FACILITY OR AT THE LOCAL TSO LOCATED AT (CONTACT 24 HOURS IN ADVANCE): 1170 HOWELL MILL RD NW, ATLANTA, GA 30318.

ALL UNUSED AND REQUESTED SALVAGED MATERIAL TO BE RETURNED TO SAME ADDRESS.

2.3 THE RECEIPT OF ALL MATERIALS SHALL BE CONSTRUED AS CONCLUSIVE EVIDENCE THAT THE INSTALLER HAS MADE ALL NECESSARY EXAMINATION AND INSPECTIONS, AND IS SATISFIED AS TO THE QUALITY AND QUANTITY OF MATERIALS RECEIVED.

2.4 ANY AND ALL MATERIALS THAT MAY BECOME LOST, STOLEN OR DAMAGED SHALL BE REPLACED BY THE INSTALLER AT HIS SOLE EXPENSE, AND ANY DELAY INCURRED SHALL NOT BE CAUSE FOR AN EXTENSION IN TIME.

2.5 ALL UNUSED MATERIALS SUPPLIED BY FLOCK SAFETY BUT NOT USED IN THE COMPLETION OF WORK SHALL BE RETURNED TO FLOCK SAFETY FOURTEEN (14) DAYS AFTER INSTALL COMPLETION. FLOCK SAFETY WILL ARRANGE FOR THE TRANSPORTATION OF THESE MATERIALS.

3.0 PERMITS

3.1 FLOCK SAFETY HAS OBTAINED OR WILL OBTAIN PERMITS FROM DEPARTMENTS AND/OR AGENCIES OF CITIES, COUNTIES, STATES, FEDERAL GOVERNMENT, RAILROAD OR OTHER ENTITIES. WHICH PROVIDE FOR THE PLACING OF PIPES AND/OR CABLE UNDER DITCH, TRACKS AND ROADS AND PLACING PIPES AND/OR CABLE ALONG AND WITHIN PUBLIC OR PRIVATE ROAD RIGHTS OF WAY AND RAILROAD RIGHTS.

3.2 CONTRACTOR SHALL OBTAIN ADDITIONAL PERMITS, IF REOUIRED, FOR EOUIPMENT ACCESS OR MOVEMENT ON PUBLIC ROADS AND RAILROADS. COPIES OF SUCH PERMITS SHALL BE FURNISHED TO FLOCK SAFETY.

3.3 ALL TRAFFIC CONTROL, IF APPLICABLE, SHALL BE IN ACCORDANCE WITH LOCAL, STATE, COUNTY, OR PERMITTING AGENCY LAWS, REGULATIONS, AND REQUIREMENTS, AND WILL BE THE INSTALLER'S RESPONSIBILITY. TRAFFIC CONTROL PLANS PROVIDED BY CURRENT GENERAL DESIGN STANDARDS.

4.0 SAFETY AND PRECAUTIONS

4.1 ALL PERSONNEL ARE REQUIRED TO ABIDE BY ALL RULES AND REGULATIONS SET FORTH IN THE FLOCK SAFETY REQUIREMENTS, RAILROAD SAFETY CODE AND GOVERNING **JURISDICTION**

4.2 THE WORK UNDER THIS INSTALLATION WILL BE CONSTRUCTED ALONG RIGHTS OF WAY THAT MAY CONTAIN EXISTING AND OPERATIONAL UTILITIES. THE CONTRACTOR SHALL BE FULLY RESPONSIBLE FOR LOCATING EXISTING UTILITIES AND FOR COMPLIANCE WITH THE REOUIREMENTS OF ANY STATEWIDE AND/OR LOCAL AREA IN ADVANCE OF ANY EXCAVATION, BORING OR PLACING WORK AND THE CONTRACTOR SHALL LOCATE AND EXPOSE BY HAND ALL EXISTING SUBSURFACE PLANT. ANY DAMAGE CAUSED BY THE CONTRACTOR SHALL BE REPAIRED BY THE CONTRACTOR AT HIS SOLE EXPENSE AND ANY DELAY INCURRED SHALL NOT BE CAUSE FOR AN EXTENSION IN THE TIME OF THE CONTRACT.

4.3 INSTALLER SHALL BE RESPONSIBLE FOR THE PROTECTION AND MAINTENANCE OF PUBLIC AND PRIVATE PROPERTIES. INSTALLER SHALL PROTECT, SHORE, BRACE, SUPPORT AND MAINTAIN ALL UNDERGROUND PIPES, CONDUITS, DRAINS AND OTHER SUBSURFACE STRUCTURES UNCOVERED OR OTHERWISE AFFECTED BY THE WORK.

4.4 INSTALLER SHALL BE RESPONSIBLE FOR ALL DAMAGE TO STREETS, ROADS, HIGHWAYS, SHOULDERS, DITCHES, EMBANKMENTS, CULVERTS, BRIDGES OR OTHER PUBLIC OR PRIVATE PROPERTY OR FACILITY, REGARDLESS OF LOCATION OR CHARACTER, WHICH MAY BE CAUSED BY THE WORK, OR BY MOVING, HAULING, OR OTHERWISE TRANSPORTING EQUIPMENT, MATERIALS OR WORKERS TO OR FROM WORK OR ANY SITE THEREOF, WHETHER BY THE CONTRACTOR OR SUBCONTRACTORS.

4.5 DURING ALL PHASES OF CONSTRUCTION, THE INSTALLER SHALL MAINTAIN WORK AREAS IN A NEAT AND ORDERLY MANNER. CONSTRUCTION EQUIPMENT, MATERIAL AND SUPPLIES THAT ARE STORED ON THE RIGHT OF WAY SHALL NOT RESTRICT ACCESS TO SUCH RIGHT OF WAY OR THE RIGHT OF WAY ITSELF.

5.0 SECURITY

5.1 INSTALLER IS RESPONSIBLE FOR ALL SECURITY REQUIRED TO PROTECT HIS WAREHOUSE, LAYDOWN, AND STAGING AREA AND THE USE OF OUTSIDE PLANT WORK. SECURITY SHALL ALSO INCLUDE TRAFFIC CONTROL WHERE REQUIRED INCLUDING THE USE OF OFF DUTY POLICE OFFICERS.

6.0 STAKING AND SCHEDULING

6.1 ALL STAKING WILL BE PROVIDED BY FLOCK SAFETY, REOUIRED RIGHT OF WAY CLEARING SHALL BE COMPLETED PRIOR TO STAKING: THEREFORE, THE INSTALLER SHALL COORDINATE ALL CLEARING AND PLACING OPERATIONS WITH THE FLOCK SAFETY PROJECT SUPERVISOR TO AVOID DELAYS AND INTERFERENCE.

6.2 FLOCK SAFETY WILL PROVIDE RAILROAD, FLAGMEN AND SIGNALMEN AS REQUIRED; HOWEVER, THE CONTRACTOR SHALL BE REQUIRED TO COORDINATE ITS NEEDS FOR SUCH SIGNALMEN AND FLAGMEN WITH FLOCK SAFETY.

6.3 IN ADDITION TO THE SCHEDULING REQUIREMENTS IN THE GENERAL PROVISIONS, UPON REQUEST THE CONTRACTOR SHALL ALSO SUBMIT TO THE FLOCK SAFETY PROJECT SUPERVISOR, DAILY CREW ASSIGNMENT REPORTS SPECIFYING CREW AND CREW COMPOSITION AND WORK LOCATION.

7.0 SPECIAL CONSIDERATIONS


7.1 IN THE EVENT OF HIRING A CONTRATOR; DURING THE BIDDING PROCESS THE CONTRACTOR SHOULD CONSIDER THE FOLLOWING ITEMS:

7.1.1 ALL WASTE AND/OR ABANDONED MATERIALS TO BE REMOVED SHALL BE DISPOSED OF AT A "RECOGNIZED DUMP FACILITY" IN THE AREA AS DESIGNATED BY THE LOCAL GOVERNING AUTHORITY.

[THIS SPACE LEFT INTENTIONALLY BLANK FOR STAMP]					
COUNTRY CLUB MEADOWS					
1237 ANTIETAM DR, LONG GROVE, IL 60047					
fiock safet 1170 HOWELL MILL ROAD SUITE 2 ATLANTA, GA 30318	_				
REV DATE BY DESCRIPT	ION				
0 12/15/2022 DAW PRELIN	1				
I HEARBY CERTIFY THIS DOCUMENT WAS PREPARED BY MYSELF OR MY DIRECT SUPERVISION THAT I AM A DULY REGISTERED ENGINE UNDER THE LAWS OF THE STATE OF ILLINOIS.	UNDER				
[THIS SPACE LEFT INTENTIONALLY BLANK FOR STAMP]					
LICENSE PLATE READER CAMERA INSTALLATION CASE NUMBER: 00259323 PERMITTING JURISDICTION:					
VILLAGE OF LONG GROVE					
	S				
VILLAGE OF LONG GROVE COVER SHEET & LOCATION MAP SHEET: GN.02 0					


Sheet	Sheet Name		Lng	Street
A.01	#01 RFD Country Club Dr - Inbound	42.16057765	-88.0074853	1776 Checker Rd, Long Grove
A.02	#02 Schaeffer Rd SB - Inbound	42.16792342	-87.99942944	1237 Antietam Dr, Long Grove

/e, IL 60047				
ve, IL 60047				
		(THIS SPACE LEFT IN	TENTIONALLY B	LANK FOR STAMP]
		COUNTRY	CLUB M	EADOWS
		1237 ANTI GRO	IETAM D VE, IL 60	
		70 HOWELL		AD SUITE 210 30318
	REV	DATE	BY	DESCRIPTION
	-	-	-	-
	-	-	-	-
	-	-	-	-
	0	12/15/2022	DAW	PRELIM
	I HEARI MY	BY CERTIFY THIS DOCUN DIRECT SUPERVISION TI UNDER THE LAW	HAT I AM A DULY	ARED BY MYSELF OR UNDER REGISTERED ENGINEER E OF ILLINOIS.
		[THIS SPACE LEFT IN	TENTIONALLY B	LANK FOR STAMP]
			TALLATIO	0259323
		VILLAGE (
		OVER SHEE	T & LOC	ATION MAPS
		SHEET:	-	REV:
		GN.03		0



THIS DOCUMENT HAS BEEN DRAWN BASED OFF THE MOST RECENT AVAILABLE DATA & AERIAL IMAGERY. THIS INCLUDES RIGHT OF WAY, EXISTING UTILITIES, & PRIVATE PROPERTY LINES. IT REMAINS THE RESPONSIBILITY OF OTHERS TO VERIFY & CONFLICTS ABOVE & BELOW GRADE. ALL CONSTRUCTION TO FOLLOW VILLAGE OF LONG GROVE GENERAL GUIDELINES. DO

	[THIS SPACE LEFT IN	TENTIONALL'	Y BLANK FOR STAMP]
$\left \right $	COUNTRY	CLUB	MEADOWS
		IETAM VE, IL 6	DR, LONG 60047
	70 HOWELL		afety OAD SUITE 210 X 30318
REV	DATE	BY	DESCRIPTION
	-	-	-
- 	-	-	-
- -	-	-	-
ı ⊢—	+		1
O	12/15/2022	DAW	PRELIM
	BY CERTIFY THIS DOCUM	MENT WAS PR	PRELIM REPARED BY MYSELF OR UNDER LIV REGISTERED ENGINEER ATE OF ILLINOIS.
	EY CERTIEY THIS DOCU DIRECT SUPERVISION T UNDER THE LAV	MENT WAS PR	REPARED BY MYSELF OR UNDER
	BY CERTIFY THIS DOCU DIRECT SUPERVISION T UNDER THE LAV	MENT WAS PR HAT I AM A DU NG OF THE ST	YEPARED BY MYSELF OR UNDER JLY REGISTERED ENGINEER ATE OF ILLINOIS.
	EV CERTIEY THIS DOCU DIRECT SUPERVISION T UNDER THE LAV UNDER THE LAV ICENSE PLAT ICENSE PLAT INS CASE NU PERMITTIN		Y BLANK FOR STAMP
	EV CERTIEY THIS DOCU DIRECT SUPERVISION T UNDER THE LAV UNDER THE LAV INTER SPACE LEFT IN ICENSE PLAT INS CASE NU PERMITTIN VILLAGE (MENT WAS PR HAT I AM A DU NG OF THE ST UNDER THE ST TE REA TALLAT MBER: NG JUR OF LON	Y BLANK FOR STAMP DER CAMERA FION 00259323 ISDICTION:
	EV CERTIEY THIS DOCU DIRECT SUPERVISION T UNDER THE LAV UNDER THE LAV INTER SPACE LEFT IN ICENSE PLAT INS CASE NU PERMITTIN VILLAGE (MENT WAS PR HAT I AM A DU NG OF THE ST UNDER THE ST TE REA TALLAT MBER: NG JUR OF LON	Y BLANK FOR STAMP DER CAMERA TION 00259323 ISDICTION: NG GROVE



THIS DOCUMENT HAS BEEN DRAWN BASED OFF THE MOST RECENT AVAILABLE DATA & AERIAL IMAGERY. THIS INCLUDES RIGHT OF WAY, EXISTING UTILITIES, & PRIVATE PROPERTY LINES. IT REMAINS THE RESPONSIBILITY OF OTHERS TO VERIFY ALL DATA PRIOR AND EXISTING SURRONDING FACILITIES TO VERIFY ALL DATA PRIOR AND EXISTING SURRONDING FACILITIES TO VERIFY ALL DATA PRIOR AND EXISTING SURRONDING FACILITIES TO VERIFY ALL DATA PRIOR AND EXISTING SURRONDING FACILITIES TO VERIFY ALL DATA PRIOR AND EXISTING UTILITIES, & PRIVATE PROPERTY LINES. IT REMAINS THE RESPONSIBILITY OF OTHERS TO VERIFY ALL DATA PRIOR AND EXISTING SURRONDING FACILITIES TO VERIFY AND EXISTING SURRONDING

		[THIS SPACE LEFT IN	TENTIONALLY B	LANK FOR STAMP]
	\bigcap	COUNTRY	CLUB M	EADOWS
		1237 ANTI GRO	ETAM D VE, IL 60	
		70 HOWELL I		AD SUITE 210 30318
1957 1	REV	DATE	BY	DESCRIPTION
1-227.	-	-	-	-
a long	-	-	-	-
and the second second	-	-	-	-
and the second	0	12/15/2022	DAW	PRELIM
	I HEARE MY	BY CERTIFY THIS DOCUM DIRECT SUPERVISION TH UNDER THE LAW	HAT I AM A DULY	ARED BY MYSELF OR UNDER REGISTERED ENGINEER E OF ILLINOIS.
- Contraction		[THIS SPACE LEFT IN	TENTIONALLY B	LANK FOR STAMP]
			TALLATIO MBER: 0 IG JURIS	0259323 SDICTION:
\square \square \square		OVER SHEE	T & LOC	ATION MAPS
$ \Psi $		SHEET: A.02		REV: 0
		7.02		

DESIGN NOTES

1. POLE AND FOUNDATIONS ARE DESIGNED IN ACCORDANCE WITH THE FOLLOWING CODES:

- 1.1. 2009/2012/2015/2018/2021 INTERNATIONAL BUILDING CODE
- 1.2. AASHTO LRFD SPECIFICATIONS FOR STRUCTURAL SUPPORT FOR HIGHWAY SIGNS, LUMIN -TRAFFIC SIGNALS, 2015 EDITION.
- 2. POLE ANALYSIS AND FOUNDATION DESIGN ARE BASED ON THE FOLLOWING CRITERIA:

Ш

С

1

- 2.1. DESIGN WIND SPEED (Vult): (SEE SECTION 2.6)
- 2.2. RISK CATEGORY:
- 2.3. EXPOSURE CATEGORY:
- 2.4. TOPOGRAPHIC CATEGORY:
- 2.5. SEISMIC DESIGN CRITERIA:
 - 2.5.1. SOIL SITE CLASS: D (ASSUMED)
 - 2.5.2. SPECTRAL RESPONSE, Ss: 1.000g (MAXIMUM)
 - 2.5.3. SPECTRAL RESPONSE, S1: 0.400g (MAXIMUM)
 - 2.5.4. SEISMIC DESIGN CATEGORY: B
- 2.6. STRUCTURE BASE REACTIONS ARE CALCULATED AS FOLLOWS:

DESIGN WIND SPEED (MPH)	<u>moment (K-FT)</u>	<u>shear (Kip)</u>	<u>axial (Kip)</u>	
115	2.70	0.280	0.160	
125	3.20	0.330	0.160	
135 (MAX)	3.70	0.380	0.160	


- 2.7. SHOULD ANY OF THE SITE-SPECIFIC PARAMETERS BE HIGHER THAN WHAT IS NOTED ABOVE, THE EOR SHALL BE CONTACTED TO PROVIDE A REVISED DESIGN.
- 3. FOUNDATIONS ARE DESIGNED BY OTHERS. FLOCK SAFETY SHALL PROVIDE THE CONTRACTOR WITH INSTALLATION SPECIFICATIONS AND GUIDELINES. CONTRACTOR IS RESPONSIBLE FOR VERIFYING SOIL CONDITIONS PRIOR TO INSTALLATION.

GENERAL & CONSTRUCTION NOTES

- 1. CONTRACTOR SHALL CONTACT DESIGNATED AGENCY TO LOCATE ALL UNDERGROUND UTILITIES PRIOR TO CONSTRUCTION.
- 2. CONTRACTOR SHALL APPLY AND OBTAIN AN APPROVED TRAFFIC CONTROL PLAN IN ACCORDANCE WITH MUTCD AND LOCAL JURISDICTION STANDARDS.
- 3. CONTRACTOR SHALL RESTORE ALL DISTURBED AREAS TO ORIGINAL SITE CONDITION TO THE SATISFACTION OF STATE DEPARTMENT OF TRANSPORTATION AND LOCAL JURISDICTION.
- 4. ALL WORK SHALL CONFORM TO APPLICABLE ELECTRICAL CODES EXCEPT WHEN STATE DEPARTMENT OF TRANSPORTATION OR LOCAL JURISDICTION STANDARDS SUPERSEDE.
- 5. POLE AND PROPOSED EQUIPMENT SHALL BE CONNECTED TO SOLID BARE BOND GROUND AND GROUNDING ROD IN POLE FOUNDATION.
- 6. ALL CONSTRUCTION SHALL BE IN ACCORDANCE WITH SPECIFICATIONS DEFINED BY THE STATE DEPARTMENT OF TRANSPORTATION OR LOCAL JURISDICTION, UNLESS SPECIFICALLY STATED OR SHOWN OTHERWISE HEREIN.


ADA COMPLIANCE NOTES

- 1. ALL SIDEWALK CONSTRUCTION SHALL BE IN ACCORDANCE WITH ADA TITLE II, STATE DEPARTMENT OF TRANSPORTATION, AND LOCAL JURISDICTION STANDARDS.
- 2. STATE DEPARTMENT OF TRANSPORTATION CURRENT EDITION STANDARDS SHALL BE USED FOR PEDESTRIAN CONTROL PLANS WHEN CLOSURE OF SIDEWALK IS REQUIRED FOR CONSTRUCTION.
- 3. MINIMUM CLEAR PEDESTRIAN ACCESS ROUTE (PAR) SHALL BE 48" WIDE.
- 4. NO OBSTRUCTION IS PERMITTED ALONG THE WIDTH OF THE SIDEWALK, UP TO AN ELEVATION OF 7'-0" ABOVE GRADE.



			-
	COUNTRY 1237 ANTI GRO	CLUB N	MEADOWS DR, LONG
	70 HOWELL		afety DAD SUITE 210 30318
REV - - - 0	DATE - - - - 12/15/2022	BY - - - - DAW	DESCRIPTION PRELIM
I HEARE MY	IY CERTIFY THIS DOCUN DIRECT SUPERVISION TI UNDER THE LAW	HAT I AM A DU	EPARED BY MYSELF OR UNDER LY REGISTERED ENGINEER ITE OF ILLINOIS.
	THIS SPACE LEFT IN	TENTIONALLY	'BLANK FOR STAMP]
		TALLAT MBER: IG JURI	00259323 SDICTION:
С	OVER SHEE SHEET: SPEC.0		REV:





THIS DOCUMENT HAS BEEN DRAWN BASED OFF THE MOST RECENT AVAILABLE DATA & AERIAL IMAGERY. THIS INCLUDES RIGHT OF WAY, EXISTING UTILITIES, & PRIVATE PROPERTY LINES. IT REMAINS THE RESPONSIBILITY OF OTHERS TO VERIFY & CONFLICTS ABOVE & BELOW GRADE. ALL CONSTRUCTION TO FOLLOW VILLAGE OF LONG GROVE GENERAL GUIDELINES. DO NOT SCALE DRAWINGS. CALL 811 PRIOR TO DIGGING.

	i				
		[THIS SPACE LEFT IN	TENTIONALLY	BLANK FOR STAMP]	
TING HARDWARE TO BE	COUNTRY CLUB MEADOWS				
DED BY FLOCK SAFETY	1237 ANTIETAM DR, LONG GROVE, IL 60047				
		fiock safety 1170 HOWELL MILL ROAD SUITE 210 ATLANTA, GA 30318			
	REV	DATE	BY	DESCRIPTION	
K.		-	-	-	
		-	-	-	
<u>ETRIC</u>	-	-	-	-	
ACKS TO BE MOUNTED V SOLAR PANEL	0	12/15/2022	DAW	PRELIM	
	HEAR	BY CERTIFY THIS DOCUN DIRECT SUPERVISION TI UNDER THE LAW	HAT I AM A DU	EPARED BY MYSELF OR UNDER LY REGISTERED ENGINEER ITE OF ILLINOIS.	
	LICENSE PLATE READER CAMERA INSTALLATION CASE NUMBER: 00259323 PERMITTING JURISDICTION: VILLAGE OF LONG GROVE				
			T & LOO		
		SHEET: SPEC.0	2	REV: 0	